

FIRE ALARM AND FIRE SUPPRESSION SYSTEM VERIFICATION AND TESTING CERTIFICATES

PURPOSE

This interpretation has been developed to give municipalities and agencies guidance regarding the requirement for fire alarm and fire suppression systems to be verified or tested after installation.

DISCUSSION

The National Building Code-2019 Alberta Edition (NBC(AE)) directs that fire alarm and fire suppression systems are to be verified tested after installation. However, there is no guidance within the NBC(AE) as to how or the person or company performing the verification is to inform the authority having jurisdiction (AHJ) about the results of the tests.

This interpretation applies to all fire suppression systems that are installed in buildings, including, but not limited to:

1. fire suppression systems for entire buildings or floor areas within buildings,
2. fire suppression systems protecting commercial cooking ventilation systems, and
3. fire suppression systems protecting spray rooms, spray booths and spray areas for flammable and combustible material spray operations.

CODE REFERENCES

FIRE ALARM SYSTEMS

1. Sentence 3.2.4.5.(2) states:

2) Fire alarm systems shall be verified in conformance with CAN/ULC-S537, "Verification of Fire Alarm Systems," to ensure they are operating satisfactorily.

2. Sentence 2.4.2.4.(1) of Division C states:

1) If a fire alarm system is to be installed in a *building* described in Sentence 2.4.2.1.(4) or (5), the *owner* shall submit evidence to the *authority having jurisdiction*, before construction begins, that they have retained a *registered engineering professional* to

- a) design the system,
- b) perform *field reviews* of the system during installation, and
- c) witness verification of the system after installation.

Unless stated otherwise, all Code references in this STANDATA are to Division B of the National Building Code-2019 Alberta Edition

Issuance of this STANDATA is authorized by
the Provincial Building Administrator

[original signed]
Paul Chang

The logo for the province of Alberta, featuring the word "Alberta" in a stylized, cursive font with a small blue square at the end of the word.

FIRE SUPPRESSION SYSTEMS

1. Sentence 3.2.5.12.(1) to (2) states:

1) Except as permitted by Sentences (2), (3) and (4), an automatic sprinkler system shall be designed, constructed, installed and tested in conformance with NFPA 13, "Installation of Sprinkler Systems." (See Note A-3.2.5.12.(1).)

2) Except as provided in Sentences (10) and (11), NFPA 13R, "Installation of Sprinkler Systems in Low-Rise Residential Occupancies," is permitted to be used for the design, construction and installation of an automatic sprinkler system installed

- a) in a building of residential occupancy throughout that
 - i) is not more than 4 storeys in building height and conforms to one of Articles 3.2.2.47. to 3.2.2.54., or
 - ii) is not more than 3 storeys in building height and conforms to Article 9.10.1.3., or
- b) in a building of care occupancy with not more than 10 occupants that is not more than 3 storeys in building height and conforms to one of Articles 3.2.2.42. to 3.2.2.46.

(See Note A-3.2.5.12.(2).)

2. Sentence 2.4.2.3.(1) of Division C states:

1) If an automatic fire suppression system is to be installed in a *building* described in Sentence 2.4.2.1.(4) or (5), the *owner* shall submit evidence to the *authority having jurisdiction*, before construction begins, that they have retained a *registered engineering professional* to

- a) design the system,
- b) perform *field reviews* of the system during installation, and
- c) witness the testing of the system after installation.

NFPA Standards

1. Article 10.2.6 of NFPA 96, "Ventilation Control and Fire Protection of Commercial Cooking Operations" states:

10.2.6 Automatic fire-extinguishing systems shall be installed in accordance with the terms of their listing, the manufacturer's instructions, and the following standards where applicable.

- (1) NFPA 12
- (2) NFPA 13
- (3) NFPA 17
- (4) NFPA 17A.

2. Article 9.1.1 of NFPA 33, "Spray Application Using Flammable or Combustible Materials" states:

9.1.1 The automatic fire protection system shall be permitted to be, and shall be installed in accordance with, any of the following:

- (1) An automatic water sprinkler system that meets all applicable requirements of NFPA 13, Standard for the Installation of Sprinkler Systems
- (2) An automatic foam water sprinkler system that meets all applicable requirements of

NFPA 16, Standard for the Installation of Foam-Water Sprinkler and Foam-Water Spray Systems

- (3) A carbon dioxide extinguishing system that meets all applicable requirements of NFPA 12, Standard on Carbon Dioxide Extinguishing Systems
- (4) A dry chemical extinguishing system that meets all applicable requirements of NFPA 17, Standard for Dry Chemical Extinguishing Systems
- (5) A gaseous agent extinguishing system that meets all applicable requirements of NFPA 2001, Standard on Clean Agent Fire Extinguishing Systems
- (6) A water mist fire protection system that meets the applicable requirements of NFPA 750

INTERPRETATION

1. CAN/ULC-S537 and the NFPA standards that apply to fire suppression systems contain requirements for performing testing and/or verification of the systems after installation is complete and before the systems are put into operation.

In order to satisfy the AHJ that the testing and verification of the fire alarm and/or fire suppression system has been performed according to the relevant standards, the person or company responsible for the verification should provide documentation to the AHJ in the form set out in Appendix A and B of this STANDATA. The documentation provided should contain the following information:

- a. the name of the person or company performing the test or verification,
- b. the name of the building owner or designer/design engineer for whom the test or verification is being done,
- c. the name of the designer,
- d. the name of the contractor who installed the system,
- e. the name of the contractor who updated the drawings and specifications to 'as-built' status,
- f. the address of the building where the system is installed,
- g. the date of installation of the system,
- h. the date on which the system was tested or verified,
- i. the codes and standards to which the system was tested or verified,
- j. the signature of the person responsible for the verification, and
- k. the professional's seal if required (see items 2 and 3 below).

In addition to the requirements listed above and set out in Appendices A and B, the various NFPA standards and CAN/ULC-S537 contain document templates for reporting on the testing and verification of fire alarm and fire suppression systems.

2. For buildings that are required by Article 2.4.2.1. of Division C to be designed and to have construction reviewed by *Registered Architectural Professionals* **and/or** *Registered Engineering Professionals*, the following conditions should be met:
 - a. the verification of the fire alarm system and the required documentation of that verification must be completed under the direction of a *Registered Engineering Professional* who, through training and experience, is familiar with the installation and functional requirements of fire alarm systems,
 - b. once the verification of the fire alarm system is complete, **the Certificate of Verification (see Appendix A) is to be sealed by the Registered Engineering Professional assuming responsibility for the verification,**
 - c. the test of the fire suppression system and the required documentation of that test must be completed under the direction of a *Registered Engineering Professional* who, through

-
- training and experience, is familiar with the installation and functional requirements of fire suppression systems, and
- d. once the test of the fire suppression system is complete, **the Certificate of Testing (see Appendix B) is to be sealed by the Registered Engineering Professional assuming responsibility for the test.**
3. For buildings that are **not** required by Article 2.4.2.1. of Division C to be designed and to have construction reviewed by *Registered Architectural Professionals* or *Registered Engineering Professionals*, the following conditions should be met:
- a. the verification of the fire alarm system and the required documentation of that verification should be completed under the direction of
- i. the person responsible for the design and/or construction review who, through training and experience, is familiar with the installation and functional requirements of fire alarm systems, or
- ii. an independent third party who, through training and experience, is familiar with the installation and functional requirements of fire alarm systems,
- b. once the verification of the fire alarm system is complete, **the Certificate of Verification (see Appendix A) should be signed by the person assuming responsibility for the verification,**
- c. the test of the fire suppression system and the required documentation of that test should be completed under the direction of
- i. the person responsible for the design and/or construction review who, through training and experience, is familiar with the installation and functional requirements of fire suppression systems, or
- ii. an independent third party who, through training and experience, is familiar with the installation and functional requirements of fire suppression systems, and
- d. once the test of the fire suppression system is complete, **the Certificate of Testing (see Appendix B) should be signed by the person assuming responsibility for the test.**

This INTERPRETATION is applicable throughout the province of Alberta.

APPENDIX A
FIRE ALARM SYSTEM VERIFICATION

Note: This Appendix does not form a mandatory part of this STANDATA.
 It should be modified as necessary to meet specific project requirements.

_____ on behalf of
Name of Company or Person Performing Verification

_____ has carried out an on-
Name of Building Owner or Designer/Design-Registered Engineering Professional
 site verification of the Fire Alarm System installed at:

_____ *Address of Installation (City/Town)*
 This verification was carried out in accordance with CAN/ULC-S537, "Verification of Fire Alarm Systems," as required by Sentence 3.2.4.5.(2) of Division B of the National Building Code-2019 Alberta Edition.

_____ hereby confirms that
Name of Company or Person Performing Verification

on _____, the Fire Alarm System as installed was reviewed for conformance with
Month/Day/Year
 drawings and specifications originally prepared by:

_____ and subsequently
Name of Designer
 updated to "As-Built" status by: _____

_____ *Name of Contractor*
 The Fire Alarm System was tested on _____ and found to be fully operational in
Month/Day/Year
 accordance with:

1. The National Building Code-2019 Alberta Edition,
2. CAN/ULC-S524-14, "Installation of Fire Alarm Systems," and
3. The Electrical Regulations made pursuant to the Safety Codes Act.

_____ *Name of Company or Person Performing Verification*

_____ *Signature of Person Responsible for Verification*

Note: Modifications of the Fire Alarm System after _____ will invalidate this
Month/Day/Year
 Verification Certificate.

 Signature of Person Assuming Responsibility for Verification

APPENDIX B

FIRE SUPPRESSION SYSTEM TEST

Note: This Appendix does not form a mandatory part of this STANDATA.
It should be modified as necessary to meet specific project requirements.

_____ on behalf of
Name of Company or Person Performing Test

_____ has carried out an on-
Name of Building Owner or Designer/Design -Registered Engineering Professional
site test of the Fire Suppression System installed at:

_____ *Address of Installation (City/Town)*
This test was carried out in accordance with the appropriate NFPA standard noted below, as required by Sentence 3.2.5.12.(1) of Division B of the National Building Code-2019 Alberta Edition .

_____ hereby confirms that
Name of Company or Person Performing Test

on _____, the Fire Suppression System as installed was reviewed for conformance with
Month/Day/Year
drawings and specifications originally prepared by:

_____ and subsequently
Name of Designer

updated to "As-Built" status by: _____
Name of Contractor

The Fire Suppression System was tested on _____ and found to be fully operational in
Month/Day/Year
accordance with:

1. The National Building Code-2019 Alberta Edition, and
2. The appropriate NFPA standard indicated below (check only one):
 - NFPA 13-2013, "Installation of Sprinkler Systems,"
 - NFPA 13R-2013, "Installation of Sprinkler Systems in Residential Occupancies up to and Including Four Stories in Height,"
 - NFPA 12-2011, "Carbon Dioxide Extinguishing Systems,"
 - NFPA 16-2011, "Installation of Foam-Water Sprinkler and Foam-Water Spray Systems,"
 - NFPA 17-2009, "Dry Chemical Extinguishing Systems,"
 - NFPA 17A-2009, "Wet Chemical Extinguishing Systems,"
 - NFPA 96-2017, "Ventilation Control and Fire Protection of Commercial Cooking Operations."

_____ *Name of Company or Person Performing Test*

_____ *Signature or Person Responsible for Test*

Note: Modifications of the Fire Suppression System after _____ will invalidate
Month/Day/Year
this Testing Certificate.

Signature of Person Assuming Responsibility for Test