

Datasheet on Polymer Flood Project (1)

Attribute	Data for the Project
Reservoir	East Bodo Upper Mannville "A" Pool (Lloyd)
Project	Associated Polymer Flood
Operator	Pengrowth Energy
Reservoir Temperature (°C)	20
Oil Density (kg/m ³)	966
Solution Gas@ P _b (m ³ /m ³)	7.2
Live Oil Viscosity (mPa.s)	3,105
Connate Water Hardness (ppm)	
Connate Water Salinity (ppm)	29,000
Average Porosity (%)	31
Average Permeability (md)	1000
Dykstra-Parsons Coefficient (V)	-
Net Thickness (m)	4.63
Connate Water Saturation (%)	34
Project Area (Ha)	54
Number of Active Producers	6
Number of Active Injectors	3
Number of Observation Wells	-
OOIP (e3m ³)	537.88
Formation Volume Factor (oil) (m ³ /m ³)	1.015
Hydrocarbon Pore Volume (HCPV) (e3m ³)	545.94
Prior to Polymer Injection	
Cumulative Oil Produced (e3m ³)	26.65
Remaining Reserves (e3m ³)	15.43
Ultimate Recovery Factor (%)	2.86
Water-Oil Ratio	1.88
Recovery Process (Polymer, ASP, SP, etc)	
Alkali Concentration (wt %)	0
Surfactant Concentration (wt %)	0
Polymer Concentration (wt %)	0.175
Main Slug Size (%HCPV)	2.8 (injection continues)
Chase Polymer Concentration (wt %)	-
Chase Slug Size (%HCPV)	-

Datasheet on Polymer Flood Project (2)

Attribute	Data for the Project
Reservoir	East Bodo Upper Mannville "A" Pool (Lloyd)
Project	Associated Polymer Flood
Operator	Pengrowth Energy
OOIP (e3m ³)	537.88
HCPV (e3m ³)	545.94
Stabilized Injection Rate (m ³ /d)	40 – 60
Time needed to inject 1 HCPV polymer (years)	30
Oil Rate Response (sustained increase) (m ³ /d)	4.5
Water-Cut Response (reduction)	7.13
Initially Expected Recovery Factor	19
Latest Indicated Recovery Factor	0.9
Polymer injected to 2011 end (e3 kg)	25.5
Incremental oil to 2011 end (e3 m ³)	5.0
Polymer utilization to 2011 end (kg/ inc. Oil-m ³)	5.1
Ultimate polymer to be injected (e3 kg)	Yet to be determined
Ultimate Incremental oil (estimated) (e3 m ³)	34.2
Polymer Utilization (ultimate) (kg/ inc. Oil-m ³)	-
Recommended specific areas of technology focus while extending the scheme to analogous reservoirs (e.g. corrosion, injectivity, water treatment, etc)	Water treatment
Major Problems Encountered	Water treatment, stability of polymer viscosity-concentration
Major Project Accomplishments	Improvement in oil production, associated polymer injection with vertical wells
Next Planned Phase for the Project	Continue injection and monitoring